



# NOTICE (Updated 9/16/22)

## *Sewer work continuing in Delmar*

- Sections of sewer mains under Hawthorne Avenue, Adams Place, and Adams Street have been replaced (new pipe lining installation will be scheduled soon)
- Work beginning today on Delmar Place sewer pipe replacement

### WHY

The sewer mains in this area are old, with some installed as far back as 1929. During routine inspections, our crews found sections of these sewer mains that are failing and need to be replaced before they cause sewage backups into homes or sinkholes in the roadways.

### WHAT'S HAPPENING

We will excavate and replace the damaged sections of sewer main. Next, we will line the repaired pipe lines from manhole to manhole, thus creating a new pipeline that should provide reliable service for many years to come!

### TRAFFIC IMPACTS

- Roads in area of work will be closed (with local traffic allowed to get in to and out of their driveways)
- We ask that all traffic use other side streets to avoid these areas

### TIMELINE

The work should take about a month to complete:

- **Start Date:** September 12<sup>th</sup>
- **Projected End:** Friday, October 14<sup>th</sup>

### QUESTIONS/UPDATES

If you have questions, comments, or concerns, please contact:

**George S. Kansas, P.E.**

Commissioner of Public Works

518-439-4955 ext 1137

[gkansas@townofbethlehem.org](mailto:gkansas@townofbethlehem.org)

## PROJECT LOCATIONS & DESCRIPTIONS

- Intersection of Hawthorne Avenue, Adams Street, and Adams Place: 26 feet of 12-inch clay tile pipe has been replaced (lining work remains)
- 179 Adams Street: 15 feet of 15-inch clay tile pipe has been replaced (lining work remains)
- 40 Delmar Place: 30 feet of 15-inch clay tile pipe to be replaced
- 60 Delmar Place: 30 feet of 15-inch clay tile pipe to be replaced



## QUESTIONS/UPDATES

If you have questions, comments, or concerns, please contact:

**George S. Kansas, P.E.**  
Commissioner of Public Works  
518-439-4955 ext 1137  
[gkansas@townofbethlehem.org](mailto:gkansas@townofbethlehem.org)

